

LiveWall Updated Cost Calculations

Reduced Pricing Range: \$137,700 - \$229,500

[\$90-\$150 per square foot]

Breakdown of total cost:

Provided Materials for the Wall: **(\$68,850-\$114,750)** [\$45 - \$75 per square foot]

- Furrings strips and Slot Rails with irrigation conduits (RainRails)
- Irrigation main line components
- Irrigation parts and fittings from valves to the RainRails
- Wall Planters
- Removable planter inserts (empty)

Plants: **(\$15,300 - \$30,600)** [\$10 - \$20 per square foot]

- May be sourced from a local garden center or florist.
- If desired, we can arrange to have empty planter inserts shipped separately directly to your grower of choice.
- In some US locations, we can supply fully grown planted inserts.

Contactor Installation Requirements: **(\$53,550 - \$68,850)** [\$35 - \$45 per square foot]

- Fasteners for installation between LiveWall and building structure
- Facing Material to cover the irrigation feed (typically wood or sheet aluminum)
- UV Resistant Fittings and pipe from the mainline to the irrigation valves – SCH 80 Gray Pipe and Fittings recommended
- Underlying backing material
- Labor, equipment rental, and a fair profit

Other Considerations:

- Water Source
- Electrical Wiring for Controllers